
lucrari instalare centrala termica Scoala gimnaziala Cezar Petrescu Busteni

I.D.: 61536372

Data publicarii	01.10.21	Coduri CPV	45331100-7
-----------------	----------	------------	------------

Pretul estimativ: 92.294,96 RON - 92.294,96 RON

Descriere: dezafectare cazan/cazane vechi, montare 2 buc microcentrale Viessmann Vitodens 200 (model 2021), avand puterea totala de 240 kW (2x120Kw) si functie doar de incalzire, echipate cu senzori, preselector hidraulic debit 12 metri cubi/ora, pompe recirculare microcentrale 2 buc, grup siguranta individual 2 seturi (supape siguranta, vase expansiune conform Normativ I13/2015), colector comun gaze arse, set filtre impuritati, separatoare namol, tevi, conducte, vane, robineti, fittinguri, consumabile, material marunt
