

## Reparat instalatia de incalzire la subsol

I.D.: 86997769

---

Data publicarii	13.09.23	Coduri CPV	45231111-6
-----------------	----------	------------	------------

---

Pretul estimativ: 33.862,39 RON - 33.862,39 RON

---

Descriere: Demontat canal termic in doua zone pentru a avea acces la conductele ce urmeaza a fi inlocuite prin scurgere, strat 20cm beton cu picamar Dezafectat instalatia de incalzire tur-retur pe o distanta de 38m, in conditii grele de acces si manipulare a materialelor dezafectate Executat instalatie tur de agent termic (teava PP-R D75=38m, coturi, mufe, reductie metalica 3"-21/2"=2buc, stut filetat 21/2"=2buc, racord PP-R D75=2buc, teu PP-R D75-40-75=5buc, bride metalice 21/2"=20buc, tija filetata M10=10m) Executat instalatie retur de agent termic (teava PP-R D63=38m, coturi, mufe reductie metalica 3"-21/2"=2buc, stut filetat 21/2"=2buc, teu PP-R D63-40-63=5buc, bride metalice 2"=20buc, tija filetata M10=10m) Executat legaturi de la coloana genarala de agent termic la cele 5 coloane verticale (tv PP-R D40=10m, coturi, mufe, bride 11/4") Inlocuit tronson de incalzire tur-retur intrecentrala termica si subsol pe canal termic (tv din otel 4"=16m, curbe 4"=4buc) Executat probe de presiune si etanteseitate

---