

Executie bransament electric foraj apa Holod

I.D.: 75969103

Data publicarii	28.11.22	Coduri CPV	31681410-0
-----------------	----------	------------	------------

Pretul estimativ: 7.082,46 RON - 7.082,46 RON

Descriere: Pachet materiale electrice cu montare/instalare compus din: - BMPT echipat cu siguranta automata 3P 63A, $R_p < 10\Omega$, montat pe postament din poliester armat cu fibra de sticla: 1 buc, 1.500 lei/buc; - tablou ABS 40x30x21cm IP65 TN PLS: 1 buc, 200 lei/buc; - clema derivatie, fixare contranapou, gri 16-95mm: 4 buc, 49,90 lei/buc; - clema sir ind.de prot.pe sina alb 16-50mm, 150A: 4 buc, 65 lei/buc; - sina metalica omega din L-1M 02-435: 1 buc, 35 lei/buc; - presetupa din plastic cu contrapiulita 37-44mmPG48PG-48: 2 buc, 35 lei/buc; - cablu armat aluminiu ACYABY-F / AC2XABY 3x50+25: 20 m, 28,90 lei/buc; - papuc aluminiu inelar neizolat AS50-10: 3 buc, 15 lei/buc; - papuc aluminiu inelar neizolat AS25-8: 1 buc, 15 lei/buc; - realizare prize de pamant formata din 3 tarusi de 1,5 m si 7 m de platbanda zincata 40x4: 1 um, 1.328,90 lei/um; - teava otel trasa sau sudata longitudinal montata prin insurubare D 1 1/4" zincata: 2 um, 150 lei/buc; - lucrari in regim "normal": 12 ora, 212,58 lei/ora
