
Instalatie electrica Camin Cultural Berchez

I.D.: 100273936

Data publicarii	16.07.24	Coduri CPV	45310000-3
-----------------	----------	------------	------------

Pretul estimativ: 3.208,32 RON - 3.208,32 RON

Descriere: Kopoflex D40 - 3 metri Cyaby 3X16 mmp pozat in sant existent si aparent - 55 metri Sapatura de pamant mecanizata in profil M si T cu utilaj tip miniescavator JCB-sapat si astupat sant H=80, L=30, inclusiv banda avertizoare - 25 metri Teava PVC D110 SN10 - 4 metri Pat de cablu 20X20 - 3.5 metri
