
Panouri fotovoltaice 30kwp si statie incarcare autovehicule electrice 22kw Certeju de Sus 2

I.D.: 94399682

Data publicarii	06.03.24	Coduri CPV	45261215-4
-----------------	----------	------------	------------

Pretul estimativ: 178.906,46 RON - 178.906,46 RON

Descriere: Montare sistem fotovoltaic 30kW format din: - 60buc panou fotovoltaic 505W monocristalin, halfcut; - 1set structura montaj la sol - 1buc invertor 30KW trifazat - 1buc smartmeter trifazat 250W -1 buc smart WLAN-FE dongle; -500m cablu solar rosu H1Z2Z2-K 1x6 -500m cablu solar negru H1Z2Z2-K 1x6 -20buc conector MC4 KBT 4/6 II - female/positive -20buc conector MC4 KBT 4/6 II - male/negative - 400m tub protectie UV -1buc tablou TE echipat -1buc statie incarcare vehicule 22KW, 4.7m type 2 - 1buc firida distributie Parc Fotovoltaic - Statie incarcare auto- Utilizator - 1set priza de pamant - 1set alimentare firida distributie Montarea include executia traseului de cablare de la sistem la TGD existent, probe si punere in functiune.
