

## Lucrari de instalatii apa si incalzire

I.D.: 57811041

---

|                 |          |            |            |
|-----------------|----------|------------|------------|
| Data publicarii | 09.06.21 | Coduri CPV | 45332000-3 |
|-----------------|----------|------------|------------|

---

Pretul estimativ: 43.649,83 RON - 43.649,83 RON

---

Descriere: Spart beton mecanizat - 2.8 mc - 1274 ron Sapatara mecanizata de pamant - 20 mc - 704 ron Umplutura mecanizata de pamant - 20 mc - 95.40 ron Compactare mecanizata -20 mc - 201.15 ron Transport moloz cu auto - 1 cursa - 300 ron Transport utilaj - 1 cursa - 300 ron Turnat beton - 7 mc - 3472 ron Plasa sudata - 180 kg - 1250.71 ron Demontat si remontat dale de beton - 40 mp - 3379.33 ron Demontat teava otel 2 1/2" - 98 ml - 3059.66 ron Demontat teava otel 1" -46 ml - 1070.77 ron Demontat teava otel 3/4" - 46 ml - 1070.77 ron Montat teava PPR 75 mm - 98 ml - 11598,06 ron Montat izolatia Kaiflex 76x13 mm - 98 ml - 3484.73 ron Montat teava PPR 32 mm - 94 ml - 3371.14 ron Montat izolatia Kaiflex 35x13 mm - 94 ml - 2585.02 ron Montat adaptor PPR 75x2 1/2" - 4 buc - 1135.88 ron Montat adaptor PPR 32x 1" - 4 buc - 196.11 ron Montat niplu redus 1x3/4 - 2 buc - 52.53 ron Montat flansa filetata dn 50 - 4 buc - 730.38 ron Montat mufa PPR 75 mm - 14 buc - 1091.21 ron Montat mufa PPR 32 mm - 14 buc - 324.93 ron Montat cot PPR 75x90gr - 10 buc - 969.23 ron Montat cot PPR 32x90gr - 10 buc - 239.46 ron Confectionat si montat suportii - 40 kg - 788.52 ron Cheltuieli.aproviz.deplas.si.transp.mat. - 1 buc - 904.25

---