
Alte lucrari de instalare electrica

I.D.: 63127222

Data publicarii 17.11.21

Coduri CPV 45317000-2

Pretul estimativ: 18.643,35 RON - 18.643,35 RON

Descriere: Demontat lampi iluminat FIRA 2X36W - 2X18W - 50 buc. Montat Corp iluminat LED Lineer Proline - IPS 36W, 4000k IP65 120 cm - 44 buc, Corp iluminat LED Lineer Proline - IPS 18W, 4000k IP65 60 cm - 6 buc Aplica LED 20W - 2 buc. Canal cablu PVC adeziv 16x16 mm - 60 m Cablu MYYUP 2x1,5 mmp - 60 m Materiale marunte (coliere PVC , dibluri , suruburi, holsuruburi, saibe, conectori , banda izolatoare etc). Se verifica instalatia electrica de iluminat
