

Lucrari de instalare Sistem video de supraveghere in satele: Stirciu, Seredeiu si Hurez

I.D.: 43296521

Data publicarii	24.02.20	Coduri CPV	32323500-8
-----------------	----------	------------	------------

Pretul estimativ: 42.294,87 RON - 42.294,87 RON

Descriere: Lucrari de instalare sistem video de spraveghere, format din :Cameră bullet de exterior ePoE, 1/3" 4 Megapixeli Progressive scan CMOS, 25fps@4M (2688x1520), WDR (120dB) - buc 8; NVR 32 camere IP, suporta camere de max 12MP cu compresie H.265/H.264/ MJPEG/ MPEG4, redare simultana 16 canale, interfata GRID si cautare inteligenta - buc 3; HDD SATA 8TB 7200RPM 6GB/S/256MB ST8000VX0022 SEAGATE- buc 1, HDD SATA 4TB 5900RPM 6GB/S/64MB ST4000VX007 SEAGATE- buc 3; Kit accesorii montaj set 8 ELBI TABLOU ELECTRIC POLYESTER 30X40X17 buc 3 SIGURANTA AUTOMATA SCHN. ACTI9 F+N 10A 4.5KA-buc 3;Accesorii cutii metalice-buc 3 Doza de legatura IP55 universala plastic buc 6 Switch ePOE industrial, L2, 4 porturi, Capacitate maximă adrese MAC: 8.000, - buc 3 MONITOR PHILIPS 21.5" LED, 1920x1080, 5ms, 250cd/mp, vga+hdmi, panel TN, Dynamic Contrast: 10mio:1, "223V5LHSB/00" buc 4 UPS Mustek 850VA/ 480W; PowerMust 848 LCD - display LCD; 2 prize schuko; incarcare 4-6 ore; acumulator 12V/ 9Ah; AVR; back-up 120W la 20', 50% load 3', 100% load la 5"; port USB pt. PC management; suporta Windows 98/2000/2003/XP/Vista/2008, Windows 7, Linux, MAC; avertizare sonora si cu LED-uri pt. diferite stadii ale bateriei; 4.9Kg buc 3 Cablu Cat5 FTP, exterior, cu sufa, cu alimentare ml 700 Manopera instalare si setare echipamente TOTAL SISTEM (EURO fara TVA) 8,842.01 € Plata in 36 de rate egale (EURO fara TVA) 245.61 € 1 EURO = 4.7834 Lei
