

Reparat instalatia de apa calda in centrala termica si spatiul tehnic

I.D.: 102382100

| | | | |
|-----------------|----------|------------|------------|
| Data publicarii | 02.09.24 | Coduri CPV | 45231111-6 |
|-----------------|----------|------------|------------|

Pretul estimativ: 36.181,94 RON - 36.181,94 RON

Descriere: Golit instalatia de apa calda de pe fiecare coloana Dezafectat instalatia veche de apa calda Inlocuit coloana alimentare zona cabinete medicale apa calda (robinet fluture Dn100=1buc, flanse Dn100=2buc, surub M16x60=8buc, tv 21/2"=34m, curba 21/2"=5buc, stut filetat 2"=1buc, stut filetat 1/2"=2buc, robinet pe bila 1/2"=2buc, electrozi superbaz d=2,5mm=6kg, panze flex Inlocuit coloana alimentare BAI GALVANICE cu apa calda (robinet fluture Dn80=1buc, flanse Dn80=2buc, surub M16x120=4buc, tv21/2"=30m, curbe 21/2"=6buc, robinet pe bila 21/2=buc , olandez21/2=4buc, robinet 1/2"=2buc, stut 1/2"=2buc, electrozi superbaz=9kg, filtru Y 21/2"=2buc, stut 21/2"=4buc, Inlocuit coloana alimentare ZONA SPATIU TEHNICcu apa calda (TV21/2"=52M, CURBE 21/2"=7BUC, robinet fluture Dn80=1buc, flanse Dn80=2buc, surub M16x60=8buc, ELECTROZI SUPERBAZ=10KG) Inlocuit robineti nfluture de pe cele doua boilere si intrare apa calda in distribuitor 9robinet fluture Dn100=3buc) Executat 6 legaturi apa calda baigalvanice (robinet pe bila 1"=6buc, olandez PP-r D32=6buc, tv PP-R d32=12M, STUT FILETAT1"=6BUC) gRUNDUIT SI VOPSIT INTREAGA INSTALATIEI DE APA RECE NOUA EXECUTAT PROBE DE ETANSEITATE SI PRESIUNE