



EXECUTIE RIGOLA ZONA FAGET

I.D.: 71721724

Data publicarii	29.07.22	Coduri CPV	45262600-7
-----------------	----------	------------	------------

Pretul estimativ:	179.178,12 RON - 179.178,12 RON
-------------------	---------------------------------

Descriere: DESFACERE REFACERE SANT PEREAT sapatura manuala a santurilor si rigolelor - 202 m spargere manuala a fundatiei beton - 98m sapatura mecanizata - 246mc finisare manuala a taluzurilor - 737 mp cofraje beton armat - 492mp pereu din placi de beton turnat pe loc in placi separate pana la 2 m, grosime 15cm - 737mp beton B250 - 110 mc rostuirea pereului din dale prefabricate din beton - 368 m strat drenant de nisip, balast, etc grosime compactata 10cm - 737 mp transport rutier cu basculanta, autobetoniera si autocamion pe - 90 km transport manual cu roaba
