
Lucrari de instalatii electrice

I.D.: 80680170

Data publicarii	04.04.23	Coduri CPV	45310000-3
-----------------	----------	------------	------------

Pretul estimativ: 41.130,19 RON - 41.130,19 RON

Descriere: : Lucrarea cuprinde urmatoarele lucrari: strapungeri in pereti si plansee 8 buc, montare tablou electric 1 buc, montare contor trifazic 1 buc, montare siguranta automata 40A trifazic 1 buc, montare siguranta automata 32A trifazic 2 buc, montare siguranta automata 16A monofazic 11 buc, procurare prize UTP 66 buc fara montaj, montare conductor MY 3*2.5 de 400 ml, montare prize duble in canal cablu Legrand 68 buc, montaj canal cablu tip Legrand 100 ml de 10 cm* 5 cm, montare cordon cupru izolat 5*4 mmp 30 ml, montaj canal cablu fixat la pereti 30*20 mm 20 ml. Lucrarea cuprinde procurarea , transportul materialelor, cat si cheltuielile directe si indirecte.
