

## Inlocuit instalatia de incalzire cabinete medicale si vestiar bazin sulf

I.D.: 43001595

---

Data publicarii	07.02.20	Coduri CPV	45231111-6
-----------------	----------	------------	------------

---

Pretul estimativ:	9.381,56 RON - 9.381,56 RON
-------------------	-----------------------------

---

Descriere: Demontat patru radiatoare de fonta sparte si instalatia de incalzire aferenta pentru 7 calorifere Executat instalatia de incalzire tur-retur pentru 7 calorifere (teava PPR D32=24m, teava PPR D25=4M, teava PPR D20=24m, jibou 11/4"=2buc, olandez PPR D40=2buc, robinet 11/4" cu bila=2buc, robinet 3/4"=2buc, stut 3/4"=2buc, cot PPR D32D25 D20=24 buc, teu PPR D32-20-32=6buc, teu PPR D25-20-25=4 buc, record PPR D20 FE=14 buc, racord PPR D25=2buc, bride metalice D32=12buc) Echipat si montat cinci calorifere (calorifer otel 33x300x2000=2buc, calorifer otel 33x300x2200=2buc, calorifer fonta cu h=600mm=1buc, robinet tur =5buc, robinet retur =5buc, suport pardoseala =12 buc, suport calorifer fonta =4buc) Inlocuit robinetii tur-retur la doua calorifere existente Efectuat probe de presiune si etanseitate

---