

Construire gard Camin Cultural Boboc, Comuna Cochirleanca, Judetul Buzau

I.D.: 69360936

Data publicarii	20.05.22	Coduri CPV	45210000-2
-----------------	----------	------------	------------

Pretul estimativ: 49.900,00 RON - 49.900,00 RON

Descriere: Valoarea ofertata in SEAP va fi cea rezultata din rulara urmatoarelor articole de lucrari: TSA02C1 - sapatura manuala...-13,68mc; TRB01B12-transport materiale cu roaba...-24.63to; TRA01A02P-transport pamant cu autobasculanta...-24.63to; CA01A1-turnare beton...-13,68mc (include procurare 13,789mc beton B150); CB02A-cofraje din panouri ref...-32,49mp; CZ0302G1-confectionare armaturi OB37 D=6mm...-49,29kg; CZ0301K1-confectionare armaturi PC52 D=10-16mm...-236,30kg; CC01C1-Montare armaturi...-285,59kg; CA02J1-turnare beton...-2,19mc (include procurare 2,208mc beton B250); TRA06A25-transport beton...-41,48to; TRA01A25-transport materiale...-0,42to; CP03A-Montare stilpi prefabricati pt gard...-38buc (include procurare 38 stilpi prefab. beton); CMJ8D22A-montare elemente prefabricate gard...-105buc (include procurare 105 panouri prefab. beton); CL15XC-placute metalice inglobate in fundatii...-77,32kg (include procurare 77,32kg placute metalice); CL18A-Confectionare si montare stilpi porti...-160,56kg (include procurare 165,17kg profil rect patr. 150x150x5mm); CL18A-Confectionare si montare rame porti...-206,02kg (include procurare 208,08kg profil rect patr. 50x50x4mm); CL18A1-Confectionare si montare montanti porti...-66,38kg (include procurare 67,05kg profil rect patr. 20x20x2mm); TRA02A25-transport materiale...-17,74to Termen de executie: maxim 90 zile. Termen de garantie lucrare: minim 18 luni. Se va prezenta deviz oferta / situatie de lucrari la decontare.
