

Executie Retea Date - OS Baia Sprie DS MM

I.D.: 86251459

Data publicarii	25.08.23	Coduri CPV	45314320-0
-----------------	----------	------------	------------

Pretul estimativ: 5.194,50 RON - 5.194,50 RON

Descriere: Cantitate Rack 9U 600×450, montare pe perete, usa din sticla, panouri laterale detasabile si securizate , dezasamblat, culoare negru RAL 9004, DATEUP „MP.6409.9001” 1 Raft fix 19”, 1U, 300mm, fixare fata in 2 puncte, sarcina 30kg, culoare gri RAL 7035 - DATEUP „9801130400” 1 SWITCH TP-LINK 24 porturi Gigabit, carcasa metalica, rackabil TL-SG1024 1 PATCH PANEL GEMBIRD 24 porturi, Cat5e, 1U pentru rack 19”, suport posterior pt. gestionare cabluri, black, „NPP-C524CM-001” 1 ORGANIZATOR cabluri TRITON, tip masca orizontala, 19 inch, 1U, negru, „RAB-VP-X21- A1” 1 Cablu UTP Cat5e (metri liniari) 100 MESH TP-LINK, wireless, router AC1200, pt interior, 1200 Mbps, port LAN, WAN, 2.4 GHz | 5 GHz, antena externa x 2, standard 802.11ac, „Deco M4(3-pack)” 1 PATCH CORD UTP SPACER Cat5e, cupru-aluminiu, 0.5 m, negru, AWG26, „SP-PT- CAT5-0.5M-BK” 24 PATCH CORD UTP SPACER Cat5e, cupru-aluminiu, 1 m, negru, AWG26, „SP-PT-CAT5- 1M-BK” 10 Priza dubla aplicata UTP CAT5e 10 Sursa UPS 600W 1 Priza rackabila 8 posturi SCHUKO cu intrerupator 1U, PDU 8P 1 Canal cablu (jgheab) 25 x 16 mm, cu capac, 2 m, alb, PVC 5 Canal cablu (jgheab) 40 x 15 mm, cu capac, 2 m, alb, PVC 5 Canal cablu (jgheab) 60 x 40 mm, cu capac, 2 m, alb, PVC 3 Diverse materiale retea (dibluri/holzsuruburix500buc/fascete/banda iz.etc.) 1 Manopera executie retea 1
