

---

## REABILITARE CONDUCTE APA CALDA CT2 - CAMIN 1

I.D.: 63180464

---

Data publicarii	16.11.21	Coduri CPV	45231111-6
-----------------	----------	------------	------------

---

Pretul estimativ:	20.827,83 RON - 20.827,83 RON
-------------------	-------------------------------

---

Descriere: DEMONTARE TEVI OTEL - 100 M ; DEMONTARE ROBINET SERTAR - 3 BUC ; DEMONTARE ROBINET VENTIL MUFE - 3 BUC ; DEMONTARE CURBE FLANSE - 6 BUC ; TRANSPORT MATER PRIN PURTAT DIRECT - 2 T ; INCARCARE MATERIALE - 2 T ; TRANSPORT RUTIER AL PAMANTULUI - 2 T ; TEAVA DIN MAT PL - 100 M ( TEAVA PPR - 102 M ; COT PPR - 20 BUC ; MUFA PPR - 3 BUC ; REDUCTIE MF - 3 BUC ; TEU EGAL PPR - 3 BUC ; ADAPTOR PPR - 3 BUC ; APARAT SUDURA - 3,94 ORA ) ; PIEASA LEG - RAMIFICATIE DUBLA - 6 BUC ( ADAPTOR PTR FLANSA - 6 BUC ) ; MONTAJ ROBINET SFERA - 3 BUC ( ROBINET SFERIC - 3 BUC ) ; IMBINARE CU FLANSE - 6 BUC ( FLANSA CU 4 GAURI - 6 BUC ) ; ROBINET FONTA SERTAR - 3 BUC ( VANA FLUTURE DN80 - 3 BUC ; SURUB CAP HEXAGONAL-12 BUC ; PIULITA - 12 BUC ; GARNITURA - 6 BUC ) ; BRATARI FIXARE TEVI - 20 BUC ( COLIER STANDARD - 20 BUC ) ; BANDA SUPT GEMA - 4 BUC ; TIJA FILETATA - 8 BUC ; PIULITA CUPLARE - 20 BUC ; PROBA PRELIMINARA DILATARE, CONTRACTARE CONDUCTA - 100 M ; EFECTUAT PROBA ETANSARE PRESIUNE INSTAL APA CALDA, RECE - 100 ML ; INCARCAREA MATERIALELOR GRUPA A -GRELE - 1 T ; DESCARCAREA MATERIALELOR GRUPA A GRELE - 1 T TRANSPORTUL RUTIER AL MATERIALELOR - 1 T

---