

## Reparatii spatii tehnice

I.D.: 64004106

---

Data publicarii	06.12.21	Coduri CPV	45453000-7
-----------------	----------	------------	------------

---

Pretul estimativ:	46.415,61 RON - 46.415,61 RON
-------------------	-------------------------------

---

Descriere: Desfacerea...placajelor din faianta,gresie,ceramice mp 51.00 41.56 material: 0.00 manopera: 41.36 utilaj: 0.20 transport: 0.00 Demolarea betoanelor vechi prin demolari si spargeri ale betonului simplu sau armat vechi mc 1.50 915.09 material: 0.00 manopera: 915.09 utilaj: 0.00 transport: 0.00 Trasporturi cu mijloace man.:roaba pe pneuri,dist<100m,100-120kg,incl.asez.dulapilor de circulatie tona 3.10 104.79 material: 2.68 manopera: 102.11 utilaj: 0.00 transport: 0.00 Transportul rutier al molozului inclusiv taxa ecologizare tona 6.00 199.76 material: 0.00 manopera: 0.00 utilaj: 0.00 transport: 199.76 Demontare radiator din fonta, tabla sau ceramica de 0,6-1,8 mc/h buc 2.00 48.34 material: 0.00 manopera: 48.34 utilaj: 0.00 transport: 0.00 Demontare tevi, ng, pentru inst, la incalz centr, insurub set 1.00 723.80 material: 0.00 manopera: 723.80 utilaj: 0.00 transport: 0.00 Demontarea unui lavoar de faianta...inclusiv accesoriile buc 1.00 24.56 material: 0.00 manopera: 24.56 utilaj: 0.00 transport: 0.00 Demontare tevi instalatie sanitare set 1.00 723.80 material: 0.00 manopera: 723.80 utilaj: 0.00 transport: 0.00 Demontari, tamplarie (usi, ferestre, obloane, cuti rulou, masti) mp 4.00 37.22 material: 0.00 manopera: 37.22 utilaj: 0.00 transport: 0.00 Pardoseli din placi din gresie portelanata mp 49.00 194.63 material: 113.95 manopera: 80.14 utilaj: 0.54 transport: 0.00 Placaj din faianta la per.si stilpi 300x300x6mm gri deschis mp 9.00 193.75 material: 101.79 manoper manopera: 80.14

---