

## Pachet instalare retea internet

I.D.: 41934461

---

Data publicarii	12.02.19	Coduri CPV	32412110-8
-----------------	----------	------------	------------

---

Pretul estimativ: 15.117,00 RON - 15.117,00 RON

---

Descriere: Pachetul contine: Structurare retea in Liceu Centru: Corp1 P+E Necesari material: ■Cablul UTP Cat5E - 480m ■Canal cablu 2x2,5 fixare prin holzsurub - 120m ■Priza simpla aplicata retea - 10 buc ■Mufa RJ45 - 40 buc ■rack 6U - 1 buc ■Switch rack-abil 16 port - 1 buc ■UPS 800VA - 1 buc ■150 buc dibluri + holzsuruburi fi6 ■diblu+holzsuruburi fi10-4 buc -Manopera: 3 persoane/2 zile Corp 2 P+E Necesari material: •Cablul UTP Cat5E - 200m •Canal cablu 2x2,5 fixare prin holzsurub - 100m •Priza simpla aplicata retea - 10 buc •Mufa RJ45 - 70 buc •rack 6U - 1 buc •Switch rack-abil 16 port - 1 buc •UPS 800VA - 1 buc •150 buc dibluri + holzsuruburi fi6 •diblu+holzsuruburi fi10-4 buc -Manopera: 3 persoane/2 zile Corp 3 P Necesari materiale: •Cablul UTP Cat5E - 150m •Canal cablu 2x2,5 fixare prin holzsurub - 120m •Priza simpla aplicata retea - 6 buc •Mufa RJ45 - 25 buc •rack 6U - 1 buc •Switch rack-abil 16 port - 1 buc •UPS 800VA - 1 buc •150 buc dibluri + holzsuruburi fi6 •diblu+holzsuruburi fi10-4 buc -Manopera: 3 persoane/1 zi Structurare retea in Campus: Campus parter +Et1+Et2 •Cablul UTP Cat5E - 600m •Canal cablu 2x2,5 fixare prin holzsurub - 260m •Priza simpla aplicata retea - 20 buc •Mufa RJ45 - 25 buc •rack 6U - 3 buc •Switch rack-abil 16 port - 3 buc •UPS 800VA - 3 buc •200 buc dibluri + holzsuruburi fi6 •diblu+holzsuruburi fi10-12 buc - Manopera: 3 persoane/3 zile Campus corp ateliere •Cablul UTP Cat5E - 60m •Canal cablu 2x2,5 fixare prin holzsurub - 60m •Priza simpla aplicata retea - 3 buc

---