
Lucrari de remediere avarii inundatii

I.D.: 63276875

Data publicarii	18.11.21	Coduri CPV	45453000-7
-----------------	----------	------------	------------

Pretul estimativ: 19.875,00 RON - 19.875,00 RON

Descriere: Lucrari de remediere inundatie subsol: -desfundat camine =3 buc; -decolmatat camine =3 buc; -vidanjat subsol ; -inlocuit teava PVC 110 = 4X2M; -inlocuit cot PVC 110 =2 buc; -sapatura manuala perimetral fundatie =18ml x 1mh; -desfacut hidroizolatie deteriorata = 18ml x 1mh; -curatat fundatie prin slefuire =18ml x 1h; -aplicat membrana cauciucata lichida =18mlx 1mh; -montat membrana HDPE Isostud 150 cm x 25m (400g/mp); -refacut teren la forma initiala ; Total materiale +manopera
