
RELOCAT INSTALATIA DE APA RECE GENERALA

I.D.: 106310557

Data publicarii	29.11.24	Coduri CPV	45231111-6
-----------------	----------	------------	------------

Pretul estimativ: 3.194,69 RON - 3.194,69 RON

Descriere: Dezafectat instalatia de apa rece generala prin montarea unei schele intrucat se afla la inaltimea d 2,5m (instalatia are o lungime de 25m si coturi cu dimensiunea de 3''') Relocat instalatia de apa rece generala ce alimenteaza sediul adm. prin montarea unei schele cu o inaltime de 4m (teava PPR D40=20m, racord PPR D40=2buc, cot PPR D40=8buc, bride metalice 11/4''=15buc, reductie PPR D40/32=1buc, stut filetat 11/4''=1buc, robinet PPR D40=1buc) Executat instalatia de apa rece ce deserveste lavoarul din centrala termica (teava PPR D20=6m, teuPPR D40-20-40=1buc, robinet PPR D20=1buc) Efectuat probe de etanseitate la instalatia de apa rece noua
