

lucrari de montaj puffer 500 l

I.D.: 89876513

Data publicarii	24.11.23	Coduri CPV	45315000-8
-----------------	----------	------------	------------

Pretul estimativ: 9.429,00 RON - 9.429,00 RON

Descriere: OFERTA MODIFICARE INSTALATIE HIDRAULICA INCALZIRE - Montaj puffer 500 litri : > Stocator apa incalzire PUFFER P-500 PLUS > Materiale necesare montaj : > ADAPTOR FLANSA CANELAT ROSU 88.9 4 buc > AERISITOR AUTOMAT 1/2" 1 buc > COT PPR 32X90 GRD 4 buc > COT VICTAULIC 88,9mm (3") 12 buc > COT ZN 1/2"FI 6 buc > CUPLAJ RIGID D=88,9mm(3") VICTAULIC 30 buc > MANOMETRU RADIAL 1/4 50-16 bar 1 buc > NIPLU BZ 3/4"X1/2" 1 buc > NIPLU ZN 1/2" 6 buc > OLANDEZ AL 3/4" 1 buc > RACORD PPR 32X1"FE 1 buc > RACORD PPR 32X1"FI 1 buc > RACORD PPR 32X3/4"FE 1 buc > RACORD PPR 32X3/4"FI 1 buc > REDUCTIE ZN 1 1/2"X 1/2" 2 buc > ROBINET SF APA 1/2"FF 6 buc > ROBINET SF APA 3/4"FF 1 buc > STUT 3"X100 4 buc > TEAVA NG. 88,9x4 mm 8 ml > TEAVA PPR D=32 PN 20 2 ml > TERMOMETRU BiTh100,-20/+60C,100mm 1 buc > TEU ZN 1/2" 1 buc Include manopera , transport , deplasari , inlocuire butelie egalizare cu stocator PUFFER 500 LITRI mai putin
