
Lucrari instalatie sanitara

I.D.: 71257128

Data publicarii	13.07.22	Coduri CPV	45232460-4
-----------------	----------	------------	------------

Pretul estimativ: 4.200,00 RON - 4.200,00 RON

Descriere: DEMONTARE TEAVA ZINCATA DE 50 MM- 16 M -MONTAT TEAVA PPR DN=40 MM - 16 M -FITTING (COT ,REDUCTIE, MUFE) PPR LA TEVI - 9 BUC -MONTAT STUT FILETAT - 1 BUC -MONTAT SUPORTI TEAVA BANDA SLITATA CU GAURI DN=12 MM -14 BUC -DEMONTAT-MONTAT ROBINETI DE CALORIFER -TUR - 6 BUC -DEMONTAT-MONTAT INSTALATIE APA RECE MASINA DE SPALAT VASE - 1 BUC -ROBINET SERVICIU ,SIMPLU SAU DUBLU CU RACORD ,INDIFERENT MOD DE INCHIDERE ,DN=3/4 - 2 BUC -FITING (COD REDUCTIE ,MUFE) PPR- 4 BUC -INLOCUIREA UNEI BATERII MONOCOMANDA - 6 BUC -DEMONTAT/MONTAT REZERVOR WC -2 BUC
